BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of work: Estimate for Improvements to Roads and Drains at Hegadenagara in Ward No. 6.

Sl. No.	Approved Qty.	Description	Unit	Schedule B Rates KRIDL	
				In Figures	In Words
1	288.35	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/	cum	159.84	Rupees One Hundred Fifty Nine And Paise Eighty Four Only
2	172.88	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	5070.60	Rupees Five Thousand Seventy And Paise Sixty Only
3	121.04	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2015-16	Cum	6332.04	Rupees Six Thousand Three Hundred Thirty Two And Paise Four Only
4	151.20	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. No. 187/ Item No. 22.7/ PWD SR 2015-16	M	138.24	Rupees One Hundred Thirty Eight And Paise Twenty Four Only
5	1178.00	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift No. 171/ Item No. 22.7/ PWD SR 2015-16	Sqm	97.20	Rupees Ninety Seven And Paise Twenty Only
6	288.35	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	62.20	Rupees Sixty Two And Paise Twenty Only

Contractor Signature
Reg. No.
Postal Address

EXECUTIVE ENGINEER KRIDL BBMP, DIVISION, BANGALORE-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

5/6/16